# 2006 International Residential Code Errata

(Portions of text and tables not shown are affected by the errata)

## CHAPTER 3
## BUILDING PLANNING

**R301.2.2.3.2 Masonry construction.** Masonry construction shall comply with the requirements of Section 606.~~11.2~~. 12.2

## CHAPTER 8
## ROOF-CEILING CONSTRUCTION

**TABLE 804.3.1(1)** Last row, first column….1000S162-97 should be 1200S162-97

**TABLE 804.3.1(2)** Last row, first column….1000S162-97 should be 1200S162-97

**TABLE 804.3.1(3)** Last row, first column….1000S162-97 should be 1200S162-97

**TABLE 804.3.1(4)** Last row, first column….1000S162-97 should be 1200S162-97

**TABLE 804.3.1(5)** Last row, first column….1000S162-97 should be 1200S162-97

**TABLE 804.3.1(6)** Last row, first column….1000S162-97 should be 1200S162-97

**TABLE 804.3.1(7)** Last row, first column….1000S162-97 should be 1200S162-97

**TABLE 804.3.1(8)** Last row, first column….1000S162-97 should be 1200S162-97

## Appendix H
## PATIO COVERS

**AH105.1 General**….shall be provided with exits conforming to the provisions of Section ~~R310~~ R311 of this code.

## INDEX

**JOINTS, PIPE**