

2015 International Plumbing Code Errata

(Portions of text and tables not shown are unaffected by the errata)

1st through 3rd Printings (This Errata Posted: September 6, 2018)

CHAPTER 9 VENTS

919.1 General. Engineered vent systems shall comply with this section and the design, submittal, approval, inspection and testing requirements of Section ~~405.3~~ 316.

CHAPTER 9
VENTS

Table 906.1:

TABLE 906.1
SIZE AND DEVELOPED LENGTH OF STACK VENTS AND VENT STACKS

| DIAMETER OF SOIL OR WASTE STACK (inches) | TOTAL FIXTURE UNITS BEING VENTED (dfu) | MAXIMUM DEVELOPED LENGTH OF VENT (feet)* DIAMETER OF VENT (inches) | | | | | | | | | | |
|--|--|---|-----|-----|-------|-------|---|---|---|---|----|----|
| | | 1/4 | 1/2 | 2 | 2 1/2 | 3 | 4 | 5 | 6 | 8 | 10 | 12 |
| 1 1/4 | 2 | 30 | | | | | | | | | | |
| 1 1/2 | 8 | 50 | 150 | — | — | — | — | — | — | — | — | — |
| 1 1/2 | 10 | 30 | 100 | | | | | | | | | |
| 2 | 12 | | 75 | 200 | | | | | | | | |
| 2 | 20 | 30 | 50 | 150 | | — | — | — | — | — | — | — |
| 2 1/2 | 42 | 26 | 30 | 100 | 300 | | | | | | | |
| 3 | 10 | | 42 | 150 | 360 | 1,040 | | | | | | |
| 3 | 21 | — | 32 | 110 | 270 | 810 | — | — | — | — | — | — |
| 3 | 53 | | 27 | 94 | 230 | 680 | | | | | | |
| 3 | 102 | | 25 | 86 | 210 | 620 | | | | | | |
| 4 | 43 | — | 35 | 85 | 250 | 980 | — | — | — | — | — | — |
| 4 | 140 | | 27 | 65 | 200 | 750 | | | | | | |