

# GG115-14

## 403.1

**Proponent:** Mike Fischer, Kellen Company, representing self  
(mfischer@kellencompany.com)

**Revise as follows:**

**403.1 Stormwater management.** Stormwater management systems, including, but not limited to, infiltration, evapo- transpiration; vegetative roofing; rainwater harvest and runoff reuse; shall be provided and maintained on the building site.

**Reason:** Vegetative roofing is a proven stormwater management technique. Including it in the cited mitigation measures is appropriate.

**Cost Impact:** Will not increase the cost of construction.

**GG115-14: 403.1-FISCHER1165**

---