

GG256-14

807.6

Proponent: Barry Greive, Target Corporation, representing Target Corporation
(barry.greive@target.com)

Revise as follows:

807.6 Special inspections for sound transmission. An approved agency, employed by the building owner, shall furnish report(s) of test findings indicating that the results are in compliance with this section and the construction documents. Discrepancies shall be brought to the attention of the design professional and *code official* prior to the completion of that work. A final testing report documenting required testing and corrections of any discrepancies noted in prior tests shall be submitted at a point in time agreed upon by the building owner, or building owner's agent, design professional, and the *code official* for purposes of demonstrating compliance.

Exception: Special Inspections and test reports are not required for *approved* assemblies with an established sound transmission class (STC) rating.

Reason: Special inspections are not needed on assemblies that have already been tested and have an established sound rating. This is a minor change to this exception to clarify that not only the report is not needed the special inspection is not needed for these already tested assemblies. A similar proposal is submitted for 807.5. This will bring consistency to section 807.

Cost Impact: Will not increase the cost of construction.

GG256-14 : 807.6-GREIVE1115
