



What to Look for When Conducting Plan Reviews and Inspections of Solar PV

Presenter: Rudy Saporite

Tuesday, September 12, 2017

9:45 AM - 11:15 AM







ABOUT IBTS

The Institute for Building Technology and Safety is a 501(c)(3) nonprofit organization established to provide unbiased professional services, while enhancing the communities in which we work.

IBTS provides solar PV Quality Management services to some of the largest solar stakeholders in the nation. All have chosen IBTS for our industry expertise and for our proven capacity to deliver.

public sector
accountability

private sector
flexibility



MAIN COMPONENTS



Modules

Often called “Panels, Modules, or Collectors” the commonly known “Flat plate collector” type of Solar PV module is typically made up of individual Silicon cells arranged in rows laminated between a tempered glass and EVA or membrane type backsheet, mounted within an aluminum or metal frame.



Inverter(s)

Micro Inverter, String Inverter, String Inverter w/ DC Power Optimizers – Whether Module Level Power Electronics (MLPE) are utilized, or in a separate location via a string type inverter... DC power is converted to AC by an “Inverter”.



Racking

Two main types of racking are used and can generally be categorized into **traditional** and those including **integrated ground** attachments for attaching modules. Most have manufacturers recommendations for installation in order to meet the listing of the equipment that must be followed to ensure proper operation.



Balance of System (BOS) Components

Balance of System components are things such as combiner boxes, rapid shutdown equipment, breakers/fuses/disconnects, solar tracking equipment, flashing, or any other equipment that is installed to allow the PV system to integrate and operate as designed.



MODULES

Module Specifics:

Materials: Aluminum frame, tempered glass, EVA or similar backsheet, poly or monocrystalline cells, aluminum or copper conductors, ABS or similar connectors.

Mono/Poly Crystalline – Individual “Cell” construction. Mono is a single cell made from a single silicon wafer. Poly means the “cells” are made up of many smaller silicon pieces pressed together. (Polycrystalline cells have an “OSB” look to them)

Typical Configuration:

- 60 Cells (ranging from sub 200W to just over 300W)
- 72 Cells (generally 300W+)
- Cells arranged flat and encapsulated in top and backsheet.
- “Panel” on back of module with (+) and (-) leads having male and female “plug” type connectors.
- DC Output (Note: AC Modules)



INVERTERS

Inverter Specifics:

- Convert **DC** power input to **AC** power output by matching the frequency/wattage/voltage of utility. (**UL 1741 Compliance Required**)
- **Micro Inverter**
 - Often 1 per module but newer models allow for multiple.
 - Branch Circuit – circuit or chain of micro-inverters.
 - Attached to or mounted beneath PV modules.
 - Module Level Power Electronics (MLPE)
 - NEC 690.12 Rapid shutdown compliant
- **String (Central) Inverter**
 - Single inverter with inputs for multiple “strings” of PV modules.
 - Usually mounted ground level or indoors.
 - Integrated DC disconnect for all system source circuits with one single output.
 - Often times coupled with DC power optimizers (MLPE for string inverters)
- **Transformerless** (ungrounded) vs **Transformer** (grounded).

© 2017 Institute for Building Technology and Safety



RACKING

Racking Specifics:

Integrated grounding – Utilizes specifically designed attachments to create bonds and when installed to manufacturer specifications, acts as sufficient ground path bonding the modules to the EGC.

Traditional – Uses WEEBS or other module level attachments to achieve grounding.

Things to know:

- Structurally attached to roof or footing in the case of ground mount.
- Main support for system components.
- Has specific manufacturer requirements for installation to ensure bonding.
- Must show compliance with **UL 2703**
 - Specific height and spacing requirements based on fire classification.
 - Specific component classes

© 2017 Institute for Building Technology and Safety



BALANCE OF SYSTEM (BOS)

BOS Specifics:

Types

- **Combiners:** used to combine multiple strings before transition to inverter.
- **Panelboards:** branch circuit panel, subpanel, point of interconnection, etc.
- **Disconnects:** visible blade, fused, remote or rooftop
- **Monitoring:** production meter, proprietary hardware
- **Protection:** nuisance protection or netting, fencing.


Things to know:

- Components have specific installation instructions to match listing and ensure protection.
- Many components exist and some mitigate deficiencies better than others... good to research.
- Components can be newly created to address an existing issue.







COMMON FINDINGS DURING PLAN REVIEW AND PHYSICAL INSPECTIONS


What to Look for When Conducting Plan Reviews and Inspections of Solar PV



COMMON DEFICIENCIES

- 
System Labeling
20-50% Deficiency Rate. System labeling includes NEC and IFC requirements to label system components. Incorrect labels, label material not withstanding elements, incorrect system information on labels, etc.
- 
Wire Management
10-41% Deficiency Rate. Wires touching roof surfaces, exposure to UV, extended bending radius, non-wet location nuts used, conductors not fully engaged.
- 
Penetration Sealant and Flashing
10-22% Deficiency Rate. Overall building envelope protection with roof penetrations, safety anchors, racking and conduit penetrations. Improperly flashing for various roof types
- 
System/Equipment Grounding
10-15% Deficiency. Wire markings, disconnect wired improperly, and module/racking grounding.

© 2017 Institute for Building Technology and Safety




SYSTEM EQUIPMENT/GROUNDING
10-15% Deficiency

© 2017 Institute for Building Technology and Safety

COMMON GROUNDING METHODS

- ▶ **LUGS**
- ▶ **WEEBS- Stainless steel spacers with teeth for bonding aluminum components.**
- ▶ **INTEGRATED- Components designed to be grounded by mechanical fastening during installation process.**

© 2017 Institute for Building Technology and Safety



SYSTEM GROUNDING

10-15% deficiency rate



- ▶ WEEB not properly seated.
- ▶ Improper rail splice detail.
- ▶ Bare copper EGC run in contact with aluminum rack components (dissimilar metals, NEC110.14).
- ▶ EGC is not continuous to all metal system components.
- ▶ No Grounding Electrode or GEC.
 - > EGC is unnecessarily subject to damage or failure.
- ▶ Improper installation of splice or termination.

© 2017 Institute for Building Technology and Safety



SYSTEM GROUNDING



Difficult to understand if
torque requirements are met





Loose clamp not holding
module and not bonded.

© 2017 Institute for Building Technology and Safety




SYSTEM GROUNDING






Improperly seated WECC

Improperly seated WECC

© 2017 Institute for Building Technology and Safety




SYSTEM GROUNDING





Dissimilar Metals – Aluminum lug used instead of zinc plated aluminum.

Dissimilar lug used without jumper. Will result in EGC failure.


© 2017 Institute for Building Technology and Safety



SYSTEM GROUNDING




Improper EGC termination




Lugs not tightened to EGC

© 2017 Institute for Building Technology and Safety




SYSTEM GROUNDING



- ▶ NEC 690.43: Exposed non-current carrying parts of PV systems must be grounded in accordance with NEC 250.66 (AC GEC), 250.122 (EGC size) and 260.166 (DC GEC).
- ▶ NEC 110.3(B): shall be installed in accordance with any instructions included in the listing or labeling
 - > Torque requirements
 - > Inclusion of all bonding components
- ▶ Run in the same raceway with other conductors when leaving array (690.43(F))

© 2017 Institute for Building Technology and Safety




GROUNDING - A FEW NEC SPECIFICS

- ▶ Equipment Grounding Conductor Installation: NEC 250.120
 - > Minimum #6AWG if subject to physical damage
- ▶ Size of EGC: 250.122, Table 250.122
 - > Based on the size of the overcurrent protection device in the circuit
- ▶ NEC Article 690, Section V
 - > All metal parts must be grounded (690.43(A))
 - > And more...
- ▶ Ungrounded systems may use AC EGC as GEC (NEC 690.47(C)(3))
- ▶ AC system GEC- must be continuous (NEC 250.64(C))



SYSTEM GROUNDING- INTEGRATED

Manufacturers provide specific installation requirements and instructions- following these ensure compliance with UL2703 and engineered stability of racking.



BONDING CONNECTION GROUND PATHS: M
INSTALLATION GUIDE: PAGE

BONDING MIDCLAMP ASSEMBLY
1. Install the bonding plate. 2. Fit the bonding plate over the mid-clamp. 3. Tighten the bonding plate. 4. Tighten the mid-clamp. 5. Tighten the bonding plate. 6. Tighten the mid-clamp. 7. Tighten the bonding plate. 8. Tighten the mid-clamp.

BONDING ENDCLAMP ASSEMBLY
1. Install the bonding plate. 2. Fit the bonding plate over the end-clamp. 3. Tighten the bonding plate. 4. Tighten the end-clamp. 5. Tighten the bonding plate. 6. Tighten the end-clamp. 7. Tighten the bonding plate. 8. Tighten the end-clamp.

BONDING RAIL SPICE BAR
1. Install the bonding plate. 2. Fit the bonding plate over the rail splice bar. 3. Tighten the bonding plate. 4. Tighten the rail splice bar. 5. Tighten the bonding plate. 6. Tighten the rail splice bar. 7. Tighten the bonding plate. 8. Tighten the rail splice bar.

RAIL TO FOOT BONDING T-BOLT
1. Install the bonding plate. 2. Fit the bonding plate over the rail to foot bonding t-bolt. 3. Tighten the bonding plate. 4. Tighten the rail to foot bonding t-bolt. 5. Tighten the bonding plate. 6. Tighten the rail to foot bonding t-bolt. 7. Tighten the bonding plate. 8. Tighten the rail to foot bonding t-bolt.

BONDING MICROINVERTER MOUNT
1. Install the bonding plate. 2. Fit the bonding plate over the microinverter mount. 3. Tighten the bonding plate. 4. Tighten the microinverter mount. 5. Tighten the bonding plate. 6. Tighten the microinverter mount. 7. Tighten the bonding plate. 8. Tighten the microinverter mount.

BACK SYSTEM GROUND
1. Install the bonding plate. 2. Fit the bonding plate over the back system ground. 3. Tighten the bonding plate. 4. Tighten the back system ground. 5. Tighten the bonding plate. 6. Tighten the back system ground. 7. Tighten the bonding plate. 8. Tighten the back system ground.

Example, courtesy of UNIRAC SOLARMOUNT



SYSTEM GROUNDING



Bonding strip at rails splice



Lug on rail with WEED

© 2017 Institute for Building Technology and Safety



SYSTEM GROUNDING



Ground lug on rail





Lug on module with star washer


© 2017 Institute for Building Technology and Safety




SYSTEM GROUNDING




Transition to insulated, run in conduit



Myers Ground Hub




Array Conduit Grounded





Conduit Grounded


© 2017 Institute for Building Technology and Safety



SYSTEM GROUNDING




Enclosure is grounded.



Enclosure is not grounded.

© 2017 Institute for Building Technology and Safety



SYSTEM GROUNDING



EGC/GEC irreversibly connected to primary
system GEC by mechanical attachment or crimp.

© 2017 Institute for Building Technology and Safety



PENETRATION AND FLASHING

10-22% Deficiency Rate

© 2017 Institute for Building Technology and Safety

PENETRATIONS & FLASHING



10-22% deficiency rate

- ▶ Flashing not designed for roof type.
- ▶ Flashing installed improperly.
 - Improper install depth.
 - Nailed through face.
 - Broken roof material around flashing.
 - Fastener too tight causing deflection.
- ▶ No sealant or flashing used at all.
- ▶ Sealant not approved for use in location.
- ▶ Wall and under eave penetrations not sealed.


© 2017 Institute for Building Technology and Safety



PENETRATIONS & FLASHING



- ▶ Flashing should allow for critical overlap as identified by IRC.
- ▶ Installed as defined by manufacturer.
 - > Under 3rd course of shingles
 - > Not overhanging shingle below



© 2017 Institute for Building Technology and Safety



PENETRATIONS & FLASHING



Improperly Installed Flashing




Improperly Installed Flashing

© 2017 Institute for Building Technology and Safety



PENETRATIONS & FLASHING



No Flashing



Incorrect Flashing Type

© 2017 Institute for Building Technology and Safety



PENETRATIONS & FLASHING



Not Secured; Flashed?



Potential Water Entry

© 2017 Institute for Building Technology and Safety



PENETRATIONS & FLASHING



Flashed and Secured



Flashed and Secured

© 2017 Institute for Building Technology and Safety



PENETRATIONS & FLASHING



Tile roof conduit support



Low Slope Penetration Option
Chem Curb

© 2017 Institute for Building Technology and Safety




PENETRATIONS & FLASHING



Metal Roof Conduit Flashing and Supporting Options

© 2017 Institute for Building Technology and Safety






WIRE MANAGEMENT

10-41% Deficiency Rate

© 2017 Institute for Building Technology and Safety


WIRE MANAGEMENT

10-41% deficiency rate



- ▶ Conductors in direct contact with roof surface.
- ▶ Improper identification of conductor (wrong wire colors, fused strings not identified).
- ▶ AC/DC conductors sharing a trough without separation or identification.
- ▶ No bushings used at conduit entry.
- ▶ Conductors not protected from prolonged exposure.
- ▶ Splice not consistent with insulation rating.
- ▶ Conductors with improper bend radius and strained.

© 2017 Institute for Building Technology and Safety



WIRE MANAGEMENT



- ▶ Conductor management
 - > NEC 334.15: Protected from physical damage
 - > NEC 334.24: Radius of inner curve of bend shall not be less than 5 times diameter
 - > NEC 334.30: Secured every 4.5ft and within 12" of enclosures, conduit entry points
 - > NEC 690.31(B): Clearly grouped and identified (points of termination, connection and splice points)
 - > NEC 110.14(B): Spliced adequately

© 2017 Institute for Building Technology and Safety



WIRE MANAGEMENT



- ▶ Conductor Identification
 - > NEC 200.6: grounded conductors must be white, gray or 3 striped (#6AWG ≥)
 - > NEC 250.119: EGC must be green bare, or green with yellow stripes (#6AWG ≥)
 - > NEC 310.110: Ungrounded- must be distinguishable from grounded and EGC
 - > NEC 690.31(B): AC and DC must be separated, grouped, identified


© 2017 Institute for Building Technology and Safety



WIRE MANAGEMENT



Wires Touching Roof Surface



Conductor strung up tightly between modules with UV exposure.

© 2017 Institute for Building Technology and Safety



WIRE MANAGEMENT



Splice not consistent with conductor rating



Incorrect Splice of Ground

© 2017 Institute for Building Technology and Safety



WIRE MANAGEMENT



No Conduit Used on Rooftop



Unmanaged conductors beneath a ground mount array. Left readily accessible on "commissioned" system.

© 2017 Institute for Building Technology and Safety



WIRE MANAGEMENT



AC and DC Unidentified and Unmanaged





No Strain Relief or Conduit Bushing


© 2017 Institute for Building Technology and Safety




WIRE MANAGEMENT




Oxide Inhibitor in Wire Nut-
OK



Wet Rated Lugs- Preferred




Line Side Splice



Coloring of Conductors

© 2017 Institute for Building Technology and Safety



WIRE MANAGEMENT





► Conduit installation as it effects wiring; PVC Expansion



© 2017 Institute for Building Technology and Safety




"DIS" HONORABLE MENTION



[Download](#)

© 2017 Institute for Building Technology and Safety



"DIS" HONORABLE MENTION



Fire caused by wire chaffing on sharp edge of metal

Photos Courtesy of Standard Solar Inc.


© 2017 Institute for Building Technology and Safety



SOMETHING TO CONSIDER WHEN ADOPTING NEW CODE



© 2017 Institute for Building Technology and Safety



SYSTEM LABELING
20-50% Deficiency Rate

© 2017 Institute for Building Technology and Safety

SYSTEM LABELING

20-50% deficiency rate



- ▶ Handwritten or illegible.
- ▶ Labeling is present but values are not present or are incorrect.
- ▶ Improper identification of hazard (AC vs. DC, Grounded vs. Ungrounded).
- ▶ Labels not suited for location or falling off, faded.
- ▶ Labels are missing.

© 2017 Institute for Building Technology and Safety



WARNINGS AND LABELING



- ▶ Shall meet the requirements of 110.21(B)
- ▶ Field Applied Hazard Marking
 - > (1) Must effectively warn personnel (words, colors, symbols)
 - Info. Note: ANSIZ535.4-2011: .12" tall and visible from a safe viewing distance form the hazard
 - > (2) Permanently affixed and not handwritten
 - Exception: if likely to change, can be handwritten (NA)
 - > (3) Must be durable enough to handle environment where in stalled

© 2017 Institute for Building Technology and Safety



What to Look for When Conducting Plan Reviews and Inspections of Solar PV

SYSTEM LABELING

[Download](#)

© 2017 Institute for Building Technology and Safety

SOURCES:

NATIONAL ELECTRIC CODE 2014, NFPA, 2014

“MIKE HOLT’S ILLUSTRATED GUIDE TO DIRECTORY, IDENTIFICATION, LABEL, MARKING, PLAQUE AND SIGN REQUIREMENTS FOR SOLAR PV SYSTEMS”, MIKE HOLT, FREE ONLINE DOWNLOAD 2016

NEW LABELS BRING CLARITY TO PV INFRASTRUCTURE, TODD FRIES, SOLAR INDUSTRY MAGAZINE, ZACKIN PUBLICATIONS- 2013, ACCESSED 2016

UNDERSTANDING THE NEC AND ITS IMPACT ON PV SYSTEMS, SOLARPRO, REBEKAH HREN AND BRIAN MEHALIC, ISSUE 7.3 APRIL/MAY 2014



CONTACT US
www.ibts.org

Rudy Saporite

Program Manager, Energy & Sustainability
rsaporite@IBTS.org

Sarah Leighty

Solar Project Manager – Review, Inspection
and Training
sleighty@IBTS.org

Richard Lawrence

Program Director, Energy & Sustainability
rlawrence@IBTS.org

Paul Hancher

Director, Building Department Services
phancher@IBTS.org

